

ARCHITECHNICS, INC.  
510 MAINE STREET  
QUINCY, ILLINOIS 62301

PROJECT NO. : 5661A

**ADDENDUM NO.:** 2

ISSUED: 12/8/2017

Project: EXTERIOR ENTRY REPLACEMENT  
BROWN COUNTY COURTHOUSE  
200 EAST COURT STREET  
MOUNT STERLING, ILLINOIS 62353

This addendum becomes a part of the bidding and contract documents and modifies the drawings and specifications dated November 17, 2017. Acknowledge receipt of this addendum by noting such on the Contractor's Proposal (Bid) Form.

FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION

ITEM	DESCRIPTION
------	-------------

**DRAWINGS / SPECIFICATIONS:**

1.0	Sheet A4	Revise:	Revise Detail 1: The concrete piers for the new GFRC columns may be installed from the foundation up to the Top of Concrete Base elevation. This would allow the piers to be installed separate from the exterior concrete flatwork. Should this option be utilized, the exterior concrete flatwork shall be epoxy doweled into the concrete piers with #4x18" dowels @ 18"0.c. around the perimeter of the column pier.
2.0	Sheet A4	Revise:	Revise Detail 1: The GFRC column shall be anchored to the concrete base with (4) post installed connections. Each connection shall be comprised of a L4X4X3/16X0'-4" angle with (1) 5/8" diameter expansion anchor into the concrete and (2) screws into the GFRC base.

This addendum consists of 1 pages. Attachments: None