

**ADDENDUM**

Client: Quincy Public Schools District #172  
 Project Name: Health Life Safety Work: Electrical Systems Replacement at: Quincy Junior High School  
 Project Number: 5901  
 Addendum Number: 2  
 Issued: 4/14/2020

This addendum becomes a part of the bidding and contract documents and modifies the drawings and specifications dated March 20, 2020. Acknowledge receipt of this addendum by noting such on the Contractor's Proposal (Bid) Form.

**FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION**

This addendum and all future addenda with a Plan Holders List will be also be posted on the website of Architechnics and updated daily. Check the Contractors link on the site: [www.architechnicsinc.com](http://www.architechnicsinc.com)

ITEM	DESCRIPTION	NOTES
------	-------------	-------

**General:**

**Bids are due to the QPSD 172 District office. Due to the social distancing guidelines issued by the state and federal government the public bid opening will not be available to attend in person. Please drop your bid off ahead of time at the security counter and you can view the bid opening at the link below.**

[meet.google.com/hsw-cuws-cbf](https://meet.google.com/hsw-cuws-cbf)

At contractor's option bonding costs can be coordinated with the district and separated based on the amount of work to be completed each Summer. Bid bond shall cover the entire bid.

Wireless control system shall be capable of communicating through walls, floors, ceilings, etc. Any additional nodes, communication devices, etc required for a complete working system shall be included in the bid.

Contractor shall verify each ceiling height with the district prior to install. Contractor shall install all blocking, framing, etc required for installation around piping, windows, etc.

Any conduits in corridors that need to be installed before ceilings and ahead of the phases listed can be coordinated with the district.

**DRAWINGS:**

E102, E302	Revise	E102, Keyed note #16. New fixtures in Upper Gym shall be installed in new ceiling and grid with tectum or equal flat, square edge ceiling tiles. At contractor's option the existing ceiling hanging wires can be re-used. Verify spacing and install additional wires as required. Existing Upper Gym T-Bar grid can be re-used (contractor verify compatibility with new ceiling tiles). Contractor shall paint existing grid if re-used and replace any damaged/bent sections.
------------	--------	---

This addendum consists of 2 pages.