

# ARCHITECHNICS

architects • engineers • interior designers

## ADDENDUM

Client: VIT CUSD 2

Project Name: Renovations to Track

Project Number: 6159

Addendum Number: 02

Issued: 09-07-2021

---

This addendum becomes a part of the bidding and contract documents and modifies the drawings and specifications dated August 25, 2021. Acknowledge receipt of this addendum by noting such on the Contractor's Proposal (Bid) Form.

### FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION

This addendum and all future addenda with a Plan Holders List will be also be posted on the website of Architechnics, Inc. and updated daily. Check the Current Projects tab on the site: [www.architechnicsinc.com](http://www.architechnicsinc.com)

| ITEM             | DESCRIPTION | NOTES   |
|------------------|-------------|---|
| <b>DRAWINGS:</b> |             |   |
| General          | Add/Clarify | Shot Put Pad shall be 7'-0" diameter. Discus pad shall be 8'-2 1/2" diameter. Any concrete pads or pavement alternate/deduct prices shall have #4 rebar @12" O.C. in both directions with min. 10" total turned down slab at edges. |

This addendum consists of 1 page.