

ARCHITECHNICS, INC.
510 MAINE STREET
QUINCY, ILLINOIS 62301

PROJECT NO. : 6181

ADDENDUM NO.: 2
ISSUED: 02/12/24

Project: Mechanical Systems Replacement at
Quincy Senior High School - Building E
3322 Maine Street
Quincy, Illinois 62301

This addendum becomes a part of the bidding and contract documents and modifies the drawings and specifications dated January 25, 2024. Acknowledge receipt of this addendum by noting such on the Contractor's Proposal (Bid) Form.

FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION

ITEM	DESCRIPTION		
<u>General</u>			
1.0	Roof mounted Heat Recovery Units: In addition to the owner removing parts (compressors, etc.) from these units, owner will evacuate and maintain the refrigerant for their own purposes prior to unit(s) removal by contractor.		
<u>Specifications</u>			
1.0	Section 09 5100 Acoustical Ceilings	Add	Ceiling tile: equal to CertainTeed HHF-457 DP (2x2x3/4) and HHF-497 DP (2x4x3/4); fine fissured, high NRC; trim edge.
2.0	Section 23 0713 Duct Insulation	Add	In addition to duct liner as specified, contractor has the option to externally wrap all interior supply ductwork with R-6 duct wrap insulation equal to Johns Manville Microlite FSK. Supply and return air ductwork from the AHU to the top of the duct shaft shall have duct liner as specified for noise control. Supply ductwork beyond that point may be wrapped as stated. Exterior ductwork shall be lined, wrapped and covered as specified.
3.0	Section 26 5000 Lighting Fixtures	Revise	Para. 1.7.B.1 & .2 - replace 5 years with 10 years.
<u>Drawings</u>			
1.0	S502 Detail 9	Add	In lieu of concrete infill over the duct shaft opening, contractor has option of using: 8", 18 ga. metal studs, 1.625 flange, with (2) layers of Type X drywall on top side. Provide double studs at perimeter of duct openings.

Attachments: None